

2020 STREET MAINTENANCE PROGRAM UPDATE

Glendening Drive: Work begins about 25-feet east of the intersection with Hendron Road and will continue east to the entrance to Glendening Middle School. Curbs and gutters will be removed and replaced, driveway aprons removed and reconstructed, with asphalt milling and resurfacing with spot base repair. Sidewalk curb ramps will be replaced. A new pedestrian crossing warning system will also be installed near the entrance to Glendening Elementary School.

Concrete Work (curbs and gutters and drive aprons) is scheduled to begin on or around May 22, 2020 (depending on weather) and continue for approximately 14 days. Street paving is expected to be completed in early to mid-June.

South Hamilton Road: Work begins at the intersection of London-Groveport Road and will continue south to the corporation limit, near Lowry Court. Work to include asphalt milling and resurfacing with spot base repair, and improve the shoulders. Raised pavement markers will also be removed and installed.

Pavement milling is scheduled to begin on or around May 26, 2020 and improvements will continue until around mid-June.

East Bixby Road: Work begins at the intersection of South Hamilton Road and will continue east to a point about 250 feet east of Dorchester Street. A full-depth pavement reclamation will occur between the Cruiser Park parking lot and a point west of the Dorchester Street intersection that requires a temporary road closure. A detour route (along Ebright Road, Corbett Road and S. Hamilton Road) will be posted with signage in advance of the road closure, with updates posted on the City's website. The contractor advises that the detour will be in place between about one to three weeks. Asphalt milling and resurfacing with spot repairs will also be included along Bixby Road.

The detour and work are scheduled to begin on or around May 26, 2020, depending on weather. All work is scheduled to be completed by mid-June.

Main Street and College Street: The intersection will be improved with new crosswalk treatment, new pavement markings and brick sidewalk restoration. The curb ramps will be improved to meet American Disabilities Act requirements. The contractor will also mill and repave the intersection, and make minor drainage repairs as needed.

Crosswalk work at Main Street and College Street will begin in early July and continue for approximately 14 days.

Various locations will also be improved with crack seal, spot repairs and pavement markings.

(Continues on back)

General Comments:

During work times, traffic flow may be disrupted and some curbside parking will be temporarily discontinued. Resident notices will be posted in some work areas in advance of the work to be performed.

While weather may affect the schedule, it is anticipated that all work will begin as noted above, and may continue into late July.

Any questions may be directed to the City Municipal Building, office of the City Engineer, at 614-836-5301.

Revised May 20, 2020

